

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. McCune of Cities Service has this

date requested permission to plug the following described well:

Mr. McCune guarantees payment of the plugging fee.Operator's full Name: Cities Service Oil Co.Complete Address: Box 1228, Guymon, OklahomaLease Name: French "A" Well No. 2Location: C SE NW Sec. 12 Twp. 32 Rge. 40 XX (E) (W)County: Morton Total Depth 6176' Oil WellGas Well X Input Well SWD Well D & A X Lost HoleMr. McCune was instructed to plug the well as follows:

8 5/8" to 1706' circulated w/ cement. 4 1/2" to 5870' cemented.

Top perforations 5674' Plug bottom w/ 75 sacks cementTop of cement 4800' Mud 4800' to 1600'Spot 40 sacks cement 1600' to 1475' Mud 1475' to 40'Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent