

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jones of J.M.Huber has this

date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: J.M.Huber

Complete Address: Box 978 Liberal, Kansas

Lease Name: Krey Well No. # 1

Location: C SW Sec. 30 Twp. 32S Rge. 40 (W) (W)

County Morton Total Depth 2424' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Jones was instructed to plug the well as follows:

8 5/8"-475' Circulated w/cement. 5 1/2"-2412' Cemented. Perforations 2264'-2358'

Plug bottom w/20 Sax.cement top cement 2150'. Mud 2150' to 500'

35 Sax.cement 500' to 400' Mud 400' to 45'

15 Sax.cement 45' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent