

10  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1966  
GUY...  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Texaco Incorporated

Complete Address: 614 Bitting Building, Wichita, Kansas

Lease Name Emma McJones Well No. 1

Location C SW SE Sec. 16 Twp. 33 Rge. 29 ~~(XX)~~ (W)

County Meade Total Depth 5872'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargent Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5:30PM Day 26 Month 2 Year 1966

The Above well was plugged as follows:

16" Casing to 209' circulated w/cement. 10 3/4" to 1499' circulated w/cement.

7" to 5871' cemented. Top perforations 5758'

Plug Bottom w/25 sacks cement, Top cement 5661'

Mud 5661' to 700' Spotted 50 sacks cement 700' to 600'

Mud 600' to 40' Plug, hulls & 20 sacks cement 40' to 0

Pulled 3030' of 7" Casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: E. J. Eves  
Well Plugging Supervisor

DATE 3/1/66

INV. NO. 2802-4