

15-119-10002-0000

Form CP-3
Rev. 6-4-68

KANSAS

sc
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Powell & Stone
Complete Address Box 768, Woodward, Oklahoma 73801
Lease Name Banker Well No. 1
Location 135' E of G SE NE Sec. 19 Twp. 33 Rge. 29 (E) (W)
County Meade Total Depth 5954'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 4:00PM Day 8 Month 6 Year 1972

The above well was plugged as follows:
8 5/8" to 1551' circulated w/ cement. 5 1/2" to ^{5874'} ~~5574'~~ Cemented
Top perforations 5799' Plug bottom w/ 25 sacks cement.
Top of cement 5600' Mud 5600' to 900'
Spot 35 sacks cement 900' to 800' Mud 800' to 45'
Plug. Halls & 15 sacks cement 45' to 0'. Company Pump
Pulled 1401' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edgar Evers*
Well Plugging Supervisor

DATE 6-13-72
INV. NO. 5870-W