

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company
Complete Address Box 358, Liberal, Kansas
Lease Name Singley Well No. 1
Location SE NE Sec. 20 Twp. 33 Rge. 29 ~~(E)~~ (W)
County Meade Total Depth 5988'
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling Co.
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 2:00PM Day 12 Month 2 Year 1970

The above well was plugged as follows:

13 3/8" to 673' circulated w/ cement. 8 5/8" to 2731' cemented.
5 1/2" to 5988' cemented. Top perforations 5871'
Plug bottom w/ 20 sacks cement Top of cement 5720'
Mud 5720' to 600' Spotted 50 sacks cement 600' to 525'
Mud 525' to 25' Plug, Halls & 15 sacks cement 25' to 0'.
Company Pump Pulled 3027' of 5 1/2" casing.
Pulled 1007' of 8 5/8" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar E. Eder
Well Plugging Supervisor

INVOICED

DATE 2/16/70
INV. NO. 1437-W