

KANSAS

Al
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company

Complete Address Box 358, Liberal, Kansas 67901

Lease Name Shinogle Well No. 2

Location E/2 NW Sec. ²⁰29 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 6014'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 7 Month 2 Year 1970

The above well was plugged as follows:

8 5/8" to 1525' circulated w/ cement. 5 1/2" to 6014' cemented.

Top perforations 5780' Plug bottom w/ 20 sacks cement.

Top of cement 5610' Mud 5610' to 900'

Spotted 35 sacks cement 900' to 800'. Mud 800' to 45'

Plug. Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3027' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edward J. Fisher*
Well Plugging Supervisor

DATE 2/11/70
INV. NO. 1402-W