

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: Box 649 Mc/Cook, Nebraska.

Lease Name E.M. Eckhoff Well No. # 1

Location SW SW SW Sec. 25 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5838'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 5 PM Day 5 Month 8 Year 63

The Above well was plugged as follows:

<u>8 5/8" 1459' Circulated w/950 Sax.cement.</u>	<u>5 1/2" 5838' Cemented W/300 Sax.cement.</u>
<u>Plug Back To 5695' w/cement.</u>	<u>Perforations 5666' to 5682'</u>
<u>Sand 5695' to 5200'</u>	<u>20 Sax.cement 5200' to 5060'</u>
<u>Mud 5060' to 700'</u>	<u>Rock Bridge 700' to 690'</u>
<u>35 Sax.cement 690' to 590'</u>	<u>Mud 590' to 50'</u>
<u>Rock Bridge 50' to 40'</u>	<u>15 Sax.cement 40' to surface.</u>
<u>Weld Cap On Surface.</u>	<u>Pulled 2600' 5 1/2" Pipe. Company Pump.</u>

I hereby certify that the above well was plugged as herein stated.

INVOICED

D. 8/7/63
INV. NO. 9531-W

Signed: *Flugh Scott*
Well Plugging Supervisor