



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kaiser-Francis

Complete Address 420 4120 E. 51st, Tulsa, Oklahoma

Lease Name Cordes Well No. 1

Location SW SW NW Sec. 25 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5820' 5824

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 9:00AM Day 25 Month 5 Year 1974

The above well was plugged as follows:

8 5/8" to 1497' d rulated w/ cement. 5 1/2" to 5819' cemented.

Top perforations 5656' Plug bottom w/ 20 sacks cement.

Top of cement 5540' Mud 5540' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2744' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Lee*
Well Plugging Supervisor

DATE 5/30/74

INV. NO. 9198-W

INVOICED