

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-119-20542 ✓ *K*

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720 Fourth Financial Center Wichita, Kans. 67202

Lease Name Heinson Well No. 1-28

Location C-N $\frac{1}{2}$ -S $\frac{1}{2}$  Sec. 28 Twp. 33S Rge. 29W (East)(West)

County Meade Total Depth 6140'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sage Drilling Co. Inc.

Address 220 Sutton Place Wichita Kansas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 6:45 PM Day: 8 Month: December Year: 19 81

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

There is 1544' of 8 $\frac{3}{8}$ " surface casing cement circulated. The  
anhydrate bottomed at 1430'. 1st plug push rubber plug  
to 1520' then pumped 70 lbs of cement on top of it, 2nd plug  
at 600' with 50 lbs of cement. 3rd plug is solid  
bridge at 40' to 0' with 10 lbs of cement. Then pumped  
5 lbs each in 4 at hole + mouse hole. Halliburton  
Co. out of Liberal Kansas accomplished the plugging.  
The cement used was Common cement

INVOICE RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above plugging instructions were given as herein stated.

DATE: 12082 DEC 11 1981  
INV. NO. 8975-W 12-11-81  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Paul Luthie  
Conservation Division Agent