

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1963
1963
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name Behnke Well No. 02-29

Location C SW SW Sec. 29 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 6000'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 8 PM Day 13 Month 8 Year 63

The Above well was plugged as follows:

8 5/8"-1640'-Circulated w/cement. 4 1/2"-5950'-Circulated w/cement.

Bottom Plug w/Baker Bridge Plug.at 5220' Mud 5220' to 700'

Plug, 35 Sax.cement 700' to 600' Mud 600' to 60'

Rock Bridge 60' to 50' 15 Sax.cement 50' to surface.

Cut off surface. Weld cap on surface. Pulled 3195' 4 1/2" Pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/15/63

INV. NO. 9584-W

Signed: Hugh Scott
Well Plugging Supervisor