

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling Co.

Complete Address 211 N. Broadway, Wichita, Kansas

Lease Name Ballard Well No. 1-31

Location ~~APP 6 SE 30 SW~~ NW SE SW Sec. 31 Twp. 33 Rge. 29 (EX) (W)

County Meade Total Depth 5926'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 30 Month 12 Year 1971

The above well was plugged as follows:

8 5/8" to 1477' circulated w/ cement. 5 1/2" to 5926' cemented.

Top perforations 5841' Plug bottom w/ 25 sacks cement.

Top of cement 5606' Mud 5606' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2820' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward E. Green
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4946-W