

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CSW SE

SEC. 31 TWP. 33S RGE. 29W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Adams "A"

Operator White Eagle Oil Company Address First National Building,
Tulsa, Oklahoma

Field Adams Ranch County Meade

Total Depth 6200 Feet.

(Describe briefly the manner in which the well was plugged)

13" OD 50# Casing set at 628' with 500 sacks of cement & 8- 5/8"

32# casing set at 2780 feet with 300 sacks of cement.

8-5/8" Casing shot off at 834 feet. Cement plugs placed

at 5544-5924, 4044-4420, 2540-2920 feet. Dumped 25 sacks

of cement at 300 feet, set rock bridge and finished mudding

hole. Dumped 15 sacks of cement at surface.

3-17-52

C. A. Stough
District Conservation Agent

Date February 13, 1952

PLUGGING
FILE SEC 31 T 33 R 29W
BOOK PAGE 147 LINE 18