

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351 Liberal, Kansas

Lease Name Hall Well No. 1

Location C SW NE Sec. 35 Twp. 34 Rge. 42 XOE (W)

County Morton Total Depth 4720'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 7:00PM Day 12 Month 2 Year 1966

The Above well was plugged as follows:

8 5/8" to 1408' Circulated w/ cement. 5 1/2" to 4703' Cemented

Top Perforations 4644' Plug Bottom w/ 20 sax cement.

Top of cement 3940'- Mud 3940' To 700'

Spotted 35 sax cement 700' to 600' Mud 600' to 45'

Plug, hulls & 15 sax cement 45' to 0' Company Pump

Pulled 3230' of 5 1/2 " Casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 2/15/66

INV. NO. 2726-W