

KANSAS

FORM CP-3  
Rev. 1-8-82

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT REPORT

RECEIVED  
STATE CORPORATION COMMISSIONAPI Number 15-(none)

MAY 25 1982

5-25-82

CONSERVATION DIVISION  
Wichita, Kansas200 Colorado Derby Building  
Wichita, KS 67202Operator's Full Name Anadarko Production Co.Complete Address Box 351 Liberal Kans. 67901Lease Name Westerfield Well No. 4Location C-NE-SE Sec. 35 Twp. 34 Rge. 42 (East)(West)County Morton Total Depth 5023'Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A 

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargant's Casing PullingAddress Box 506 Liberal Kansas License No. 511Operation Completed: Hour: 2:00 PM. Day: 17 Month: May Year: 1982Plugging Operations attended by Agent?: All  Part  None 

The above well was plugged as follows:

They set 5020' of 5 1/2" and some time later squeezed it just below the surface casing filling it to top. The well was plugged back to 4999'. The perforations were from 4576' to 92'. 1st plugged off bottom with 2 bbls bulk & 6 bbls of cement. 2nd plug perforated 5 1/2" at 2500' & squeezed it with 25 bbls of cement. 3rd at 1400' with 40 bbls of cement. 4th plug at 600' with 25 bbls of cement. 5th plug 40' to 0' with 10 bbls of cement. All cement was pumped through production pipe & accomplished by Sargant's casing pulling.

Amount of Surface Casing: 1472' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I had wells in my area plugging the same time

Signed: Paul A. Luthie  
Conservation Division AgentINVOICED  
DATE 5-25-82INV. NO. 298-W