

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Texaco Incorporated has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Texaco Incorporated

Complete Address: 614 Bitting Building, Wichita, Kansas

Lease Name: Emma McJones Well No. 1

Location: G SW SE Sec. 16 Twp. 33 Rge. 29 ~~(E)~~ (W)

County Meade Total Depth 5872' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

16" Casing to 209' Circulated w/ cement. 10 3/4" to 1499' circulated w/ cement.

7" to 5871' cemented. Top Perf. 5758' Plug bottom w/ 25 sacks cement,

Top of cement 5661'. Mud 5661' to 700', Spotted 50 sacks -

cement 700' to 600' Mud 600' to 40'

Plug, Hulls & 20 sacks cement 40' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent