

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 23 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Panhandle Eastern has this
date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828, Liberal, Kansas 67901

Lease Name: Moller Well No. 2-19

Location: NE SE Sec. 19 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 6040' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

8 5/8" to 1617' circulated w/ cement. 5 1/2" to 6013' cemented.

Top perforations 5752' Plug bottom w/ 50 sacks cement.

Top of cement 5483' Mud 5483' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 50'

Plug, Halls & 15 sacks cement 50' to 0'

Very truly yours,

Edward Johnson
Conservation Division Agent