

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

MAY 4 1960

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ Location: C 5/4 SE
County: Meade Sec. 19 Twp. 33 Rge. 29 (E) (W)
Name of Field or Pool: _____ Total Depth: ~~5976~~ 6000'
5926'

I have this date completed supervision of plugging of:

Well No. 1 Lease Mollens
Operator's Full Name Pandora's Eastern Pipe Lines Co.
Complete Address: Box 979, Liberal, Kan.
Plugging Contractor: Dave Downing Drilling Co.
Address: Borgue Texas License No. _____
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

If well is a rotary drilled dry hole did operators wait for you to arrive _____
If yes how long _____ Reason: _____

Operation Completed: Hour 5pm Day 22 Month April Year 1960

The above well was plugged as follows:

1651' of 8 5/8" surface casing. Pumped 75 sack cement on bottom through tubing. Top cement 5315'. Pulled production casing. Filled hole with heavy mud to 530'. Set bridge to 540'. Spuffed 20 sack cement on bridge. Filled hole to 55' with mud. Set 20' bridge to 95'. Filled hole to surface with cement.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: [Signature]
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Reviewed: [Signature] Field Supervisor
Signed: _____ DATE 5/6/60
INV. NO. 120/11 Well Plugging Supervisor

Remarks: