

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird Supply has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: Box 358, Liberal, Kansas

Lease Name: Singley Well No. 1

Location: Sth NE Sec. 20 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 5988' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

13 3/8" to 673' circulated w/ cement. 8 5/8" to 2731' cemented.

5 1/2" to 5988' cemented. Top perforations 5871'

Plug, bottom w/ 20 sacks cement Top of cement 5720'

Mud 5720' to 600' Spot 50 sacks cement 600' to 525'

Mud 525' to 25' Plug, Halls & 15 sacks cement 25' to 0'.

Weld plate on 13 3/8" casing.

Very truly yours,

Edgar J. Eves
Conservation Division Agent