



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1970

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird Supply has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: Box 358, Liberal, Kansas

Lease Name: Shinogle Well No. 2

Location: E/2-NW SWNESE Sec. ²⁰29 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 6014' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1525' circulated w/ cement. 5 1/2" to 6014' cemented.


Top perforations 5780' Plug bottom w/ 20 sacks cement.

Top of cement 5610' Mud 5610' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent