



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird Supply Co. has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: Box 358, Liberal, Kansas

Lease Name: Shinogle "B" Well No. 1

Location: C NW SW Sec. 20 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 6028' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1625' circulated w/ cement. 5 1/2" to 6028' cemented.

Top perforations 5780' Plug bottom w/ 20 sacks cement.

Top of cement 5610' Mud 5610' to 900'

Spot 35 sacks cement 900' to 800'. Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent