



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird Supply has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Company

Complete Address: Box 358, Liberal, Kansas 67901

Lease Name: H. A. Holmes Well No. 1

Location: C SE NW SW NE SW Sec. 21 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 5949 ⁵⁹⁴⁹ 5924' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1541' circulated w/ cement. 5 1/2" to 5944' cemented.

Top perforations 5860' Plug bottom w/ 20 sacks cement.

Top of cement 5650' Mud 5650' to 900'

Spot 35 sacks cement 900' to 800'. Mud 800' to 45'.

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. [Signature]
Conservation Division Agent