



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird Supply has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Co.

Complete Address: Box 358, Liberal, Kansas 67901

Lease Name: Bender Well No. 1

Location: NE SE SW Sec. 21 Twp. 33 Rge. 29 ~~(E)~~ (W)

County: Meade Total Depth 5975' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1592' circulated w/ cement. 5 1/2" to 5885' cemented.

Top perforations 5855' Plug bottom w/ 20 sacks cement.

Top of cement 5700' Mud 5700' to 1000'.

Spott 35 sacks cement 1000' to 900' Mud 900' to 45'.

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent