



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Dix of Skelly Oil Company has this  
 date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: Box 649 Mc/Cook, Nebraska

Lease Name: E.M. Eckhoff Well No. # 1

Location: SW SW SW Sec. 25 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5838 Oil Well X

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Dix was instructed to plug the well as follows:

8 5/8" 1459' Circulated w/940 Sax.cement. 5 1/2" 5838' Cemented w/300 Sax.  
Plug Back To 5695' w/cement. Perforations 5666' to 5682'  
Sand 5695' to 5200' 20 Sax.cement 5200' to 5060'  
Mud 5060' to 700' Rock Bridge 700' to 690'  
35 Sax.cement 690' to 590' Mud 590' to 50'  
Rock Bridge 50' to 40' 15 Sax.cement 40' to surface.  
Weld Cap On Surface. Very truly yours,

*[Signature]*  
 Conservation Division Agent