

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of Kaiser has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.Operator's full Name: Kaiser-FrancisComplete Address: 4120 E 51st, Tulsa, OklahomaLease Name: Cordes Well No. 1Location: SW SW NW Sec. 25 Twp. 33 Rge. 29 (E) (W)County: Meade Total Depth 5820' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Miller was instructed to plug the well as follows:8 5/8" to 1497' circulated w/ cement. 5 1/2" to 5819' cemented.Top perforations 5656' Plug bottom w/ 20 sacks cement.Top of cement 5540' Mud 5540' to 1000'Spot 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent