

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Prod. Co. has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Behnke Well No. 01

Location: C SE SW Sec. 29 Twp. 33 Rge. 29 (E) (W)

County: Meade Total Depth 5960' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole _____

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1647' circulated w/ cement. 5 1/2" to 5960' cemented.

Top perforations 5782' Plug bottom w/ 20 sacks cement.

Top of cement 5600' Mud 5600' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 24 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Edward J. Eves
 Conservation Division Agent