



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Melton of Panhandle Eastern Pipe Line Co. has this

date requested permission to plug the following described well:

Mr. Melton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 828 Liberal, Kansas

Lease Name: Behnke Well No. 02-29

Location: C SW SW Sec. 29 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 6000' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Melton was instructed to plug the well as follows:

8 5/8"-1640'-Circulated w/cement. 4 1/2"-5950'-Circulated w/cement.


Bottom Plug w/Baker Bridge Plug-5220' Mud 5220' to 700'

Plug, 35 Sax.cement 700' to 600' Mud 600' to 60'

Rock Bridge 60' to 50' 15 Sax.cement 50' to surface.

Cut off surface, weld cap on surface.

Very truly yours,


 Conservation Division Agent