



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Patterson of Graham-Michaelis has this

date requested permission to plug the following described well:

Mr. Patterson guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Co.

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name: Ballard Well No. 1-31

Location: ~~App C SE SW~~ NW SE SW Sec. 31 Twp. 33 Rge. 29 (W)

County: Meade Total Depth 5926' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Patterson was instructed to plug the well as follows:

8 5/8" to 1477' circulated w/ cement. 5 1/2" to 5926' cemented.

Top perforations 5841' Plug bottom w/ 25 sacks cement.

Top of cement 5606' Mud 5606' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent