

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Anadarko Production Co. has this  
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351 Liberal, Kansas

Lease Name: Hall Well No. 1

Location: C SW NE Sec. 35 Twp. 34 Rge. 42 (W)

County Morton Total Depth 4720' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1408' Circulated w/ cement. 5 1/2 " to 4703' Cemented.

Top perforations 4644' Plug bottom w/ 20 sax cement.

Top of cement 3940' Mud 3940' to 700'

Spotted 35 sax cement 700' to 600' - Mud 600' to 45'

Plug, hulls & 15 sax cement 45' to 0' Company Pump

Very truly yours,

Edgar J. Eves  
Conservation Division Agent

~~INVOICED~~

DATE \_\_\_\_\_

INV. NO. \_\_\_\_\_