

15-119-10067-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Continental Oil Co.

Complete Address: Drawer 367 Plainville, Kansas

Lease Name E. Utz Well No. # 1

Location C SE SW Sec. 19 Twp. 32 Rge. 29 (N) (W)

County Meade Total Depth 5735'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Chase, Kansas License No. 436

Operation Completed: Hour 8 PM Day 13 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 1675' Circulated w/cement. 4 1/2" 5735' Cemented.

Plug back to 5703' Top perforations 5592'

Mud 5703' to 5200' 35 sax.cement 5200' to 4798'

Mud 4798' to 760' Rock bridge 760' to 750'.

35 sax.cement 750' to 650' Mud 650' to 50'

Rock bridge 50' to 40' 15 sax.cement 40' to surface.

Halliburton Cementing Co. Weld cap on surface. Pulled 2796' 4 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/15/63
INV. NO. 6928-4

Signed: [Signature]
Well Plugging Supervisor