

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name CRA, Inc. (Cooperative Refinery Association Inc.)

Complete Address: Drawer "C", Great Bend, Kansas

Lease Name Cox "L" Well No. # 1

Location C NE SE Sec. 24 Twp. 32 Rge. 20 (E) (W) W

County Comanche Total Depth 5250'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:00AM Day 15th Month March Year 1965

The Above well was plugged as follows:

547' of 8 5/8" surface pipe, cemented with 400 sacks. 5240' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 5205'. Top perforation
4650'. Plug was pushed to 4600', and sanded with 50', and cemented with
5 sacks. 4229' of 5 1/2" long string was recovered from the hole. Hole was
filled with mud to 300', and 10' of rock bridge, and cemented with 25
sacks. Hole was filled with mud to 40', and 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 3/16/65

INV. NO. 829-W

Signed: Archie Elving
Well Plugging Supervisor