

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name J.M. Huber Corporation

Complete Address Box 831, Borger, Texas 79007

Lease Name Lemon Well No. 1

Location SW SW NE Sec. 31 Twp. 32 Rge. 40XX (E) (W)

County Morton Total Depth 5605'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Daco Lease & Well Service

Address Borger, Texas License No. 138

Operation Completed: Hour 11:30AM Day 13 Month 12 Year 1969

The above well was plugged as follows:

8 5/8" to 2478' circulated w/ cement. 13 3/8" to 520' circulated w/ cement.

Plug back T.D. 2410' Top perforations 2308'

Plug bottom w/ 40 sacks cement. Top of cement 2192'

Mud 2192' to 660' Spotted 40 sacks cement 660' to 480'

Mud 480' to 30' Plug, Hulls & 10 sacks cement 30' to 0'.

Company Pump No Pipe Pulled

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

INVOICED

DATE 12/19/69

INV. NO. 1080-W