

15-129-10002-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*JP*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name D.J. Stone

Complete Address: 217 Town & Country Village, Palo Alto, California

Lease Name Claridge Well No. 1 94301

Location C SE Sec. 4 // Twp. 32 Rge. 41 ~~32~~ ~~33~~ (W)

County Morton Total Depth 5385'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 10:30AM Day 11 Month 6 Year 1969

The Above well was plugged as follows:

8 5/8" to 1491' circulated w/ cement. 5 1/2" to 5381' cemented.

Top perforations 5212' Plug bottom w/ 20 sacks cement

Top of cement. 5000' Mud 5000' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug. H<sub>2</sub>11s & 15 sacks cement 45' to 0'. Company Pump

Pulled 3800' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/13/69  
INV. NO. 9937-W

Signed: Edgar J. Jones  
Well Plugging Supervisor