

15-129-00072-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company
Complete Address Box 1228, Guymon, Oklahoma 73942
Lease Name French "A" Well No. 2
Location C SE NW Sec. 12 Twp. 32 Rge. 40 (E) (W)
County Morton Total Depth 6176'
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Daco Lease & Well Service
Address Borger, Texas License No. 138
Operation Completed: Hour 5:00PM Day 19 Month 3 Year 1970

The above well was plugged as follows:

8 5/8" to 1706' circulated w/ cement. 4 1/2" to 5870' cemented.
Top perforations 5674' Plug, Bottom w/ 75 sacks cement
Top of cement 4800' Mud 4800' to 1600'
Spotted 40 sacks cement 1600' to 1475' Mud 1475' to 40'
Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump
Pulled 2300' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Eves
Well Plugging Supervisor

INVOICED
DATE 3/23/70
INV. NO. 1622-w