

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 3 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation  
Complete Address: Box 507 Ulysses, Kansas  
Lease Name W.C. Light Well No. B#1  
Location C SW NE Sec. 21 Twp. 32S Rge. (E) (W) 40W  
County Morton Total Depth 5650  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A   ✓    
Other well as hereafter indicated: Test well abandoned.  
Plugging Contractor: Knight Casing Pulling Co.  
Address: Box 304 Chase, Kansas License No. 436  
Operation Completed: Hour 11 PM Day 28 Month 6 Year 62

The Above well was plugged as follows:

10 3/4" 702' cemented w/575 sax.  
4 1/2" 3408' cemented w/400 sax.  
Plug back to 2681' Squeeze back to 900'  
Dump sand w/bailer 2681 to 2500' Dump 3 sax.cement w/bailer.  
Pump heavy mud 2500' to 700' Set plug and hulls 30 sax.cement.  
Pump heavy mud to 30' Set plug, 10 sax. cement to cellar.  
Weld cap on surface pipe. Co.Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7/3/62  
INV. NO. 5303-W

Signed: Hugh Scott  
Well Plugging Supervisor