

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name J.M. HuberComplete Address: Box 978 Liberal, KansasLease Name Krey Well No. # 1Location C SW Sec. 30 Twp. 32S Rge. 40 (E) (W)County Morton Total Depth 2424'Abandoned Oil Well Gas Well X Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Sargent Casing Pulling ServiceAddress: Liberal, Kansas License No. 511Operation Completed: Hour 4 PM Day 2 Month 11 Year 64

The Above well was plugged as follows:

8 5/8"-475' Circulated w/cement. 5 1/2"-2412' Cemented. Perforations 2264'-2358'Plug bottom w/20 Sax. cement top cement 2150' Mud 2150' to 500'35 Sax. cement 500' to 400' Mud 400' to 45'15 Sax. cement 45' to 0 Pulled 1230' 5 1/2" pipe. Company pump.Cut surface off 5' below ground level and weld on plate.

I hereby certify that the above well was plugged as herein stated.

DATE

INV. NO.

Signed:

Well Plugging Supervisor