

15-175-00251-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Panhandle Eastern Pipe Line Company

Complete Address: Box 828, Liberal, Kansas 67901

Lease Name Morgan Well No. 1

Location App C SW Sec. 5 Twp. 32 Rge. 33 ~~(E)~~ (W)

County Seward Total Depth 2710'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00A Day 17 Month 11 Year 1969

The Above well was plugged as follows:

8 5/8" to 530' circulated w/ cement. 4 1/2" to 2705' cemented.

Top perforations 2616' Bottom plugged w/ sand to 1000'

Spotted 30 sacks cement 840' to 740'. Mud 740' to 550'

Spotted 35 sacks cement 550' to 450' Mud 450' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 872' of 4 1/2" casing.

Pipe was colapsed at approx 900'

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar Eves
Well Plugging Supervisor

DATE 11/24/69
INV. NO. 917-4