

CP-3

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 2 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corp.Complete Address: Box 507 Ulysses, KansasLease Name Specht Well No. # 1Location C NW NW Sec. 10 Twp. 32 Rge. 33 (E) (W)County Seward Total Depth 6112'Abandoned Oil Well Gas Well X Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Knight Casing Pulling Co.Address: Box 304 Chase, Kansas License No. 436Operation Completed: Hour 6 PM Day 30 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 751' Cemented w/725 sax. 4 1/2" 6055' Cemented.Plug back 6112' to 5800' W/cement.Heavy mud 5800' to 700'Plug and 35 sax. cement 700' to 600'Heavy mud 600' to 45'Plug and 15 sax. cement 45' to surface.(Pulled 1400' 4 1/2" Pipe.)( Company Pump.)

I hereby certify that the above well was plugged as herein stated.

DATE 10/3/62INV. NO. 5484-2Signed: [Signature]  
Well Plugging Supervisor