

15-175-00257-0000

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY - 6 1982  
CONSERVATION DIVISION  
WICHITA, KANSAS

API Number 15-

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Petromax Petroleum, Inc.

Complete Address 14 Lawrence Dr. Englewood, Colo 80110

Lease Name Vick Well No. A1

Location NENE SW Sec. 13 Twp. 32 Rge. 33 (East) (West)

County Seward Total Depth 2780'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargant's Casing Pulling Service

Address Box 506 Liberal, Kansas 67901 License No. 511

Operation Completed: Hour: 11:45 AM Day: 27 Month: April Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

They ran 2779' of 5 1/2" production pipe, with perforations from 2652' to 2718' & 2734' to 54'. 1st plug pumped to bottom with 6 sbx balls & 25 sbx of cement. Then displaced with heavy mud. 2nd plug at 576' with 25 sbx of cement & displaced with heavy mud & pumped 3rd plug at 40' to 0' with 10 sbx of cement. The production pipe was cemented from bottom to top out side of pipe. The plugging was accomplished by Sargant's casing pulling.

Amount of Surface Casing: 576' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthin  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 5-7-82

INV. NO. 128-u