



SIDE TWO

Operator Name Anadarko Petroleum Corporation Lease Name BEAVERS "D" Well # 2H  
 Sec. 36 Twp. 34S Rge. 38  East County Stevens  
 West

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken (Attach Additional Sheets.)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<b>Formation Description</b> <input type="checkbox"/> Log <input checked="" type="checkbox"/> Sample <table border="1"> <thead> <tr> <th>Name</th> <th>Top</th> <th>Bottom</th> </tr> </thead> <tbody> <tr> <td>Blaine</td> <td>1058</td> <td>1124</td> </tr> <tr> <td>Cedar Hills</td> <td>1194</td> <td>1400</td> </tr> <tr> <td>Stone Corral</td> <td>1678</td> <td>1756</td> </tr> <tr> <td>Chase</td> <td>2620</td> <td>2968</td> </tr> <tr> <td>Council Grove</td> <td>2968</td> <td>NA</td> </tr> <tr> <td>TD</td> <td></td> <td>3032</td> </tr> </tbody> </table>	Name	Top	Bottom	Blaine	1058	1124	Cedar Hills	1194	1400	Stone Corral	1678	1756	Chase	2620	2968	Council Grove	2968	NA	TD		3032
Name	Top		Bottom																				
Blaine	1058		1124																				
Cedar Hills	1194		1400																				
Stone Corral	1678	1756																					
Chase	2620	2968																					
Council Grove	2968	NA																					
TD		3032																					
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No																						
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No																						
Electric Log Run (Submit Copy.)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No																						

<b>CASING RECORD</b> <input checked="" type="checkbox"/> New <input type="checkbox"/> Used Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	24.0	657	Pozmix & Common	380	3% CC
Production	7 7/8	5 1/2	14.0	3027	Class C	255	10% DCD 20% DCD
<b>PERFORATION RECORD</b> Shots Per Foot   Specify Footage of Each Interval Perforated				<b>Acid, Fracture, Shot, Cement Squeeze Record</b> (Amount and Kind of Material Used)   Depth			
2	2638-48, 2671-2716, 2732-60, 2784-2838, 2854-87			Brk dwn w/19,060 gal 2% KCL wtr. Frac w/108,200 gal x-linked gelled 2% KCL wtr & 367,700# 12/20 sand.			2638-2887 O.A.
<b>TUBING RECORD</b>				Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Date of First Production 7/18/89		Producing Method <input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)					
Estimated Production Per 24 Hours	Oil Bbls.	Gas 1450Mcf @ 110#	Water Bbls.	Gas-Oil Ratio	Gravity		

Disposition of Gas:  Vented  Sold  Used on Lease (If vented, submit ACO-18.)

METHOD OF COMPLETION:  Open Hole  Perforation  Dually Completed  Commingled  Other (Specify) \_\_\_\_\_

Production Interval: 2638-2887 O.A.



INVOICE

HALLIBURTON SERVICES

A Halliburton Company

INVOICE NO.	DATE
785533	04/05/1989

WELL LEASE NO./PLANT NAME		WELL/PLANT LOCATION		STATE	WELL/PLANT OWNER	
BEAVERS D-2H		STEVENS		KS	SAME	
SERVICE LOCATION		CONTRACTOR	JOB PURPOSE		TICKET DATE	
LIBERAL		GABBERT & JONES #6	CEMENT SURFACE CASING		04/05/1989	
ACCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER	SHIPPED VIA	FILE NO.	
019595	JOHN SHILLING		33876	COMPANY TRUCK	74481	

ANADARKO PETROLEUM CORP  
P. O. BOX 351  
LIBERAL, KS 67905-0351

DIRECT CORRESPONDENCE TO:  
SUITE 600  
COLORADO DERBY BUILDING  
WICHITA, KS 67202-0000

PRICE REF. NO.	DESCRIPTION	QUANTITY	U/M	UNIT PRICE	AMOUNT
PRICING AREA - MID CONTINENT					
000-117	MILEAGE	10	MI	2.20	22.00
		1	UNT		
001-016	CEMENTING CASING	662	FT	539.80	539.80
		1	UNT		
030-016	CEMENTING PLUG SW ALUM TOP	8	S/8 IN	82.00	82.00
		1	EA		
504-043	PREMIUM CEMENT	150	SK	6.85	1,027.50
504-043	PREMIUM CEMENT	173	SK	6.85	1,185.05
506-105	POZMIX A	57	SK	3.91	222.87
507-210	FLOCELE	95	LB	1.21	114.95
509-406	ANHYDROUS CALCIUM CHLORIDE	8	SK	25.75	206.00
500-207	BULK SERVICE CHARGE	396	CFT	.95	376.20
500-306	MILEAGE CHRG MAT DEL OR RETURN	176.580	TMI	.70	123.61
INVOICE SUBTOTAL					3,899.98
DISCOUNT-(BID)					1,169.98-
INVOICE BID AMOUNT					2,730.00
*-KANSAS STATE SALES TAX					93.47
*-SEWARD COUNTY SALES TAX					23.36
INVOICE TOTAL - PLEASE PAY THIS AMOUNT					\$2,846.83

*Jim Sackman*

4305-2041  
10A 4-14

TERMS INVOICES PAYABLE NET BY THE 20TH OF THE FOLLOWING MONTH AFTER DATE OF INVOICE. UPON CUSTOMER'S DEFAULT IN PAYMENT OF CUSTOMER'S ACCOUNT BY THE LAST DAY OF THE MONTH FOLLOWING THE MONTH IN WHICH THE INVOICE IS DATED, CUSTOMER AGREES TO PAY INTEREST THEREON AFTER DEFAULT AT THE HIGHEST LAWFUL CONTRACT RATE APPLICABLE BUT NEVER TO EXCEED 18% PER ANNUM. IN THE EVENT IT BECOMES NECESSARY TO EMPLOY AN ATTORNEY TO ENFORCE COLLECTION OF SAID ACCOUNT, CUSTOMER AGREES TO PAY ALL COLLECTION COSTS AND ATTORNEY FEES IN THE AMOUNT OF 20% OF THE AMOUNT OF THE UNPAID ACCOUNT.

GABBERT-JONES  
DRILLERS WELL LOG

BEAVER "D" 2H  
SEC. 36-34S-38W  
STEVENS COUNTY, KANSAS

Commenced: 4-5-89  
Completed: 4-7-89  
Operator: ANADARKO PETROLEUM CORPORATION

Depth		Formation	Remarks
From	To		
0	662	Sand - Clay	Ran 16 jts of 24# 8 5/8" csg
662	1050	Sand - Redbed	LD @ 657' w/230 sks 50/50
1050	1255	Redbed	Posmix - 2% CC - 1/4# CF
1255	1385	Glorietta Sand	150 sks Common - 3% CC
1385	2355	Shale	1/4# CF
2355	3032	Lime Shale	PD @ 3:15 PM 4-5-89.
	3032 TD		Ran 73 jts of 14# 5 1/2" csg
			LD @ 3027' w/215 sks
			Class C - 20% DCD - 2% CC
			1/4# CF - 40 sks Class C
			10% DCD - 2% CC - 1/4# CF
			PD @ 9:45 PM 4-7-89.

RECORDED  
STATE COMMISSION

JAN 16 1990

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas )  
County of Sedgwick ) I, the undersigned, being duly sworn on oath, state  
that the above Drillers ' Well Log is true and correct  
to the best of my knowledge and belief and according  
to the records of this office.

GABBERT-JONES, INC.

*[Signature]*  
James S. Sutton, II --President

LOLA LENORE COSTA  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 11/21/92

Subscribed & sworn to before me this  
13th day of April 1989

*[Signature]*  
Lola Lenore Costa

LOLA LENORE COSTA  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 11/21/92

My Commission expires Nov. 21, 1992