

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lillard of Cleary Petroleum Corp. has this

date requested permission to plug the following described well:

Mr. Lillard guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum Corporation

Complete Address: 310 Kermac Bldg., Oklahoma City, Oklahoma

Lease Name: Classen Well No. 1

Location: C SE Sec. 36 Twp. 33 Rge. 27 (E) (W)

County: Meade Total Depth 6015' Oil Well

Gas Well X Input Well    GWD Well    D & A X Lost Hole   

Mr. Lillard was instructed to plug the well as follows:

8 5/8" to 1623' circulated w/ cement. 4 1/2" to 5959' cemented

Top perforations 5932' Plug bottom w/ 15 sacks cement.

Top of cement 5600' Mud 5600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 40'

Plug, Halls & 10 sacks cement 40' to 0'. XXXXXXXXXX

Very truly yours,

Edward A. Ford  
Conservation Division Agent