

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 18 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. T. F. Brown of Gabbert & Jones Inc. has this
 date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Gabbert & Jones Inc.

Complete Address: 514 Orpheum Bldg., Wichita, Kansas

Lease Name: Render Well No. # 1

Location: C W/2 SW SW Sec. 5 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4202 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

253' of 8 5/8" surface pipe, cement circulated.

Fill hole with mud to 240', 1/4 sack hulls, 1st cementing plug,

cement with 20 sacks. Fill hole with mud to 40', 2nd cementing

plug, 1/4 sack hulls, cement with 10 sacks to base cellar.

Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aukie Elving
 Conservation Division Agent