

2 040457

11-3

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,765-0000

SW SW NE, SEC. 5, T 30 S, R 2 W&E

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Light Well # B-1

Operator: Robinson Oil Company

County Sumner 91.00

Name & Address 420 R. H. Garvey Bldg.

Well Total Depth 2800 feet

300 W. Douglas

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8-5/8 feet 259

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone)

were: 4-1/2 2783.7

Perfs 2711-17' Sand to 2660' & 4 sx

PBTD 2733' 300# hulls 10 gel

100 sx 60/40

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1988
11-9-88
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 10:15 Day: 3 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT The perfs were sanded to 2660' & capped with 4 sx cement -

4-1/2" casing was recovered from 2050' - top was squeezed with 500# hulls,

10 sx gel & 100 sx 60/40 poz 2% gel.

Remarks: B. J. Titan #512752

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-17-88

INV. NO. 23007

Signed Steve Van Gieson (TECHNICIAN)