

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-20519

C SESE, SECTION 4 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 5003 735 FEET FROM S SECTION LINE
735 FEET FROM E SECTION LINE

OPERATOR McCoy Petro. Corp.
NAME & 110 S. Main # 500
ADDRESS Wichita Ks 67202.

LEASE NAME: Early Well# 1
COUNTY: Kingman 146.54
WELL TOTAL DEPTH: 4509 PB 4130'

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8 @ 236'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HERETINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corp.

ADDRESS: Medicine Lodge, KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson

COMPANY NAME: McCoy Petro Corp. PHONE: _____
WERE: 4-1/2 4223 Sand to 4034 & 4sx
Perf 4084-94 30sx 1222', 30x 689', circ 312'
PBTD 4130

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 11:00 DAY: 5 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:
The Perfs were covered with sand to 4034' & capped with
4 sx of cmt. The 4-1/2" casing was recovered from 3200'
and pulled from the wellbore - 2" tubing was run back
in to 1222' where 30 sx of cmt was spotted. The tubing
was pulled to 693' where 30 sx of cmt was spotted. The
tubing was pulled to 312' where cmt was circ to surface

REMARKS: Allied Cmt #2972 60/40 4% gel

I DID OBERVE THIS PLUGGING.

RECEIVED
MAY 27 1993
5-27-93
CONSERVATION DIVISION
WICHITA, KS

Steve Van Gieson
Steve Van Gieson (AGENT)

INVOICED

DATE 5-28-93

INV. NO. 37782