

To: 1 020367
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-4 15-119-10193-00-00 227
API NUMBER 15- Drilled 7/3/59
C SE SW, SEC. 24, T. 33 S, R. 29 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 7123

Operator: H.I., Inc.
Name & Address P.O. Box 2526
Liberal, KS 67905-2526

660 feet from S section line

3300 feet from E section line

Lease Name E.F. Harris Well # 1

County Meade 190.12

Well Total Depth 5850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1330

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9:30 a.m. Day: 2 Month: 4 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5830', PBTB 5340', Perfs at 5201-5209'

1st plug pump 25 sx cement at perfs,

2nd plug pump 50 sx cement at 1360',

3rd plug pump 30 sx cement at 700',

4th plug pump 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION

APR 10 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11 a.m. Day: 4 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT CEBP at 5340'

1st plug pumped 1 sx hulls and 25 sx cement at perfs, pressured to 1000#, displaced with mud,

2nd plug pumped 50 sx cement at 1360',

3rd plug pumped 30 sx cement at 700',

4th plug pumped 10 sx cement at 35-0'.

Remarks: Used common cement by Sargent's. Recovered 2612' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 4-22-91

INV. NO. 31631

Signed Glenn R. Barlow
(TECHNICIAN)