

8-28

2-051011

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-191-21,017-0000

SW SW, SECTION 30 TOWNSHIP 30 RANGE 1W

OPERATOR LICENSE # 5360 330 FEET FROM S SECTION LINE
4475 FEET FROM E SECTION LINE

OPERATOR Brandt Production Company
NAME & 200 W. Douglas, #700
ADDRESS Wichita, KS 67202

LEASE NAME: Edwards #1-A
COUNTY: Sumner 121.94
WELL TOTAL DEPTH: 3752'

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 456'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Long Drilling
ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 8:00a DAY: 28 MONTH: 8 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: _____
COMPANY NAME: _____ PHONE: _____

WERE: 5-1/2" set @ 3744' w/60 sx cmt & open hole to 3752' -
sand back to 3700' & 5 sx cmt - shoot & pull casing -
35 sx cmt @ 500' & 35 sx cmt @ 100'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: _____ DAY: 28 MONTH: 8 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded back to 3700' & dumped 5 sx cmt w/dump bailer
- shot & pulled 1900' of 5-1/2" csg - pulled casing to
543' & spotted 50 sx cmt - pulled csg to 153' & circ
cmt to surface.

REMARKS: United #201 40/60 poz mix

I DID OBSERVE THIS PLUGGING.

Glenn Ward
Glenn Ward (AGENT)

INVOICED

DATE: SEP 17 1990

INV. NO. 29317

8-28

FORM CP-2/3
REV. 3/90
STATE CORPORATION COMMISSION

SEP 7 1990
9-7-90
CONSERVATION DIVISION
Wichita, Kansas

MB