



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Armstrong of Yucca has this

date requested permission to plug the following described well:

Mr. Armstrong guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company

Complete Address: Box 2585, Amarillo, Texas

Lease Name: Hattie Jones Well No. 1-15

Location: 150' S C SE NW Sec. 15 Twp. 32 Rge. 33 (E) (W)

County: Seward Total Depth 6070' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armstrong was instructed to plug the well as follows:

- 8 5/8" to 1623' circulated w/ cement. Mud 6070' to 2900'
- Spot 35 sacks cement 2900' to 2800' Mud 2800' to 2500'
- Spot 35 sacks cement 2500' to 2400' Mud 2400' to 1000'
- Spot 35 sacks cement 1000' to 900' Mud 900' to 45'
- Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Lewis
Conservation Division Agent