

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sutton of Pan Handle Eastern has this
date requested permission to plug the following described well:

Mr. Sutton guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe Line Company

Complete Address: Box 828, Liberal, Kansas 67901

Lease Name: Morgan Well No. 1

Location: App C SW Sec. 5 Twp. 32 Rge. 33 (X) (W)

County Seward Total Depth 2710' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sutton was instructed to plug the well as follows:

8 5/8" to 530' circulated w/ cement. 4 1/2" to 2705' cemented.

Top perforations 2616' Bottom plugged w/ sand to 1000'

Spot 30 sacks cement 840' to 740' Mud 740' to 550'

Spot 35 sacks cement 550' to 450' Mud 450' to 45'

Plug, H₁₁s & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent