

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17827 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Rex Mayo of Red Tiger Drilling has this date requested permission to plug the following described well:

Mr. Mayo guarantees payment of the plugging fee.

Operator's full Name: Jones & Pellow Oil Company

Complete Address: 2821 NW 50th Street, Oklahoma City, Oklahoma

Lease Name: Printz Well No. 1-12

Location: C N ~~E~~ Sec. 12 Twp. 32 Rge. (E) (W) 33W

County: Seward Total Depth 2750' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Mayo was instructed to plug the well as follows:

620'--8-5/8" Surface casing, cement circulated.  
Circulated hole with heavy mud. Pulled DP to 675' and displaced  
50 sx. cement thru DP. Pulled DP, set bridge at 40' with 1/2 sack  
hulls and 15 sacks cement to bottom of cellar.

Very truly yours,

W.L. Mehl  
Conservation Division Agent