



Operator Name Mobil Oil Corporation Lease Name W. T. Becker Well # 1  
 Sec. 3 Twp. 33S Rge. 35  East  West County Stevens

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No

Formation Description  
 Log  Sample

Acid Record

Breakdown perforations with 3,000 gallons filtered #2 diesel containing 15 gal I-5. Drop 120 ball sealers through treatment.

Name	Top	Bottom
Wellington	2248	
Chase	2650	
Winfield	2733	
Council Grove	2957	
Admire	3228	
Wabaunsee	3050	
Shawnee	3780	
Lansing	4305	
Kansas City	4993	
Marmaton	5028	
Cherokee	5219	
Morrow	5715	
Chester	6049	
St. Genevieve	6300	
St. Louis	6403	

CONFIDENTIAL

RELEASED

CASING RECORD  New  Used  
 Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Percent Additives
Surface	12-1/4"	9-5/8"	36#	1815'	Class H Lite	100 610	3% CaCl2 3% CaCl2
Production	8-3/4"	5-1/2"	15.5#	6535'	Class H	400	5% KCL+5% HRLHD

PERFORATION RECORD \*see below  
 Shots Per Foot Specify Footage of Each Interval Perforated (Amount and Kind of Material Used) Depth

2	5998-6018	See above record detailed above
---	-----------	---------------------------------

TUBING RECORD Size 2-7/8" Set At 6022' Packer at 5833' Liner Run  Yes  No

Date of First Production Producing Method  Flowing  Pumping  Gas Lift  Other (explain).....

Estimated Production Per 24 Hours	Oil Bbls	Gas MCF	Water Bbls	Gas-Oil Ratio	Gravity

METHOD OF COMPLETION

Production Interval

Disposition of gas:  Vented  Sold  Open Hole  Perforation  Other (Specify) .....  
 Used on Lease

\*105 sks Lite + CaCl2  
 190 sks 50-50 POZ + 2% CaCl2

3821 M 105 sks Lite + CaCl2 190 sks 50-50 POZ + 2% CaCl2

5998-6018