

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Tucker Production Corporation API NO. 15-175-20,571-00-00
 ADDRESS 2546 West Main COUNTY Seward
Littleton, Colorado 80120 FIELD Wildcat

**CONTACT PERSON Reed Wacker LEASE Morlen
 PHONE 316-624-3767

PURCHASER _____ WELL NO. 1
 ADDRESS _____ WELL LOCATION C N/2 NE SE

2310 Ft. from South Line and
 660 Ft. from East Line of
 the SEC. 16 TWP. 34S RGE. 32W

DRILLING CONTRACTOR NRG Drilling, Inc
 ADDRESS P.O. Box 1157
Liberal, KS 67901

	1	6	

WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

PLUGGING CONTRACTOR Halliburton
 ADDRESS Highway 54 West; Liberal, Ks. 67901

TOTAL DEPTH 6440' PBTD _____
 SPUD DATE 10-29-81 DATE COMPLETED 11-14-81 D & A
 ELEV: GR2775 DF KB 2786

KCC _____
 KGS _____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

PLUG

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	23#	1541'	65/35(C1H/PozA)	600	6% gel; 2 1/4#/sx D-29, 2% CaCl ₂
					Class H	200	3% CaCl ₂

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			NONE		
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
NONE	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1981

CONSERVATION DIVISION
 Wichita, Kansas

TEST DATE:		PRODUCTION	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water % bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Producing interval(s)	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Ogallala Depth 300'
 Estimated height of cement behind pipe GI

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4576-4600'; 45, 60, 30, 60 min., had wk blo on 1st op.; died after 10 min.; no blo thru 2nd op, rec. 40' wtry DM; IH 2158#; IFP 32-32#; ISIP 1016#; FFP 32-32#; FSIP 677#; FH 2141#; BHT 101° F.			Wreford	3026 (- 240)
			Heebner	4398 (-1612)
			Toronto	4422 (-1636)
			Lansing	4563 (-1777)
			Marmaton	5238 (-2452)
			Morrow	5784 (-2998)
			Chester	5976 (-3190)
			St. Gen	6324 (-3538)
DST #2 6336-6396'; 30, 60, 60, 120 min.; had wk blo thru 1st & 2nd op; rec. 30' sli GCO; IH 3047#; IFP 50-56#; ISIP 105#; FFP 102-134#; FSIP 189#; FH 3035#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEWARD SS,

Reed A. Wacker OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:


THAT HE IS Agent FOR Tucker Production Corporation OPERATOR OF THE Morlen LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 16th DAY OF November 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Reed Wacker

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16th DAY OF November 19 81

A. J. Parnell
 NOTARY PUBLIC



MY COMMISSION EXPIRES: